

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/19/2017-18 Dated: 17-02-2018

APPROVED TENDER SCHEDULE -'B'

Item No: 21

Name of Work:- Providing Temporary Immersion Tank for lord Ganesh Idols at near Yelahanka lake in ward No:1 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri PBALAJI G.	
				Rate	Rate in Words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2016-17	Cum	517.50	319.39	Rupees Three Hundred Nineteen and Paise Thirty Nine Only
2	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2016-17)	cum	517.50	99.49	Rupees Ninety Nine and Paise Forty Nine Only
3	Code 0516-Providing Plastic Sheet (Page No xxvi/ I.768 PWD SR 2016-2017	Sqm	778.00	6.77	Rupees Six and Paise Seventy Seven Only
4	Engaging Unskilled heavy Mazdoor labour for guarding and for helping the public to immersion tank Ganesh idols and to safeguard the public during the pooja Time (including Expert swimmers) Page No LIV SI No 5 SR 2016-17	days	143.00	255.55	Rupees Two Hundred Fifty Five and Paise Fifty Five Only
5	Supply of water Through water tank for filling Tank	Each	85.00	376.20	Rupees Three Hundred Seventy Six and Paise Twenty Only
6	Providing stone dust to approach road and near immersion tank for levelling and to protect not to slipping SI No 50 Code 400 metal Component PWD SR page No II SR 2016-17	Cum	78.88	93.96	Rupees Ninety Three and Paise Ninety Six Only

Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri PBALAJI G.	
			Rate	Rate in Words
7 Hire Charges for two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 1.50 mtrs C/C Horizontal with Necessary earth work and labour (steel baricading)	Sft	8800.00	10.45	Rupees Ten and Paise Forty Five Only
8 Hire charge for Armless Plastic Chairs	Nos	1100.00	4.08	Rupees Four and Paise Eight Only
9 Hire charge for wooden Table of size 6ft x2ft	Nos	220.00	15.68	Rupees Fifteen and Paise Sixty Eight Only
10 Hire charge for supplying and running circuit service main with necessary messenger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathed aluminium wire (KPWD SR 2010-11 P.55/I.6 IIIb)	Mtrs	3509.00	9.41	Rupees Nine and Paise Forty Only
11 1321 Hire charge of 100 KVA generator including operator, Fuel transportation and Handling charges (PWD SR 2013-14(PXXXX /I.92) code No 132	hr	88.00	517.28	Rupees Five Hundred Seventeen and Paise Twenty Seven Only
12 Hire Charges for Shamiyana side wall of 8ft high (Size 15ftx20ft=300sqft)	Rft	3080.00	2.09	Rupees Two and Paise Nine Only
13 Hire charge for Shamiyana with Necessary Bambo Poles Erection Charges Including transportation (Size 15ftx20ft=300sqft)	Sft	3080.00	5.23	Rupees Five and Paise Twenty Two Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.